

Tender No. :- PMD-FI-4.1.1450 / Tender dated 13-01-2019

Puncom invites sealed quotations from reputed experienced contractors as per below mentioned details.

1. **TYPE OF WORK** : The sealed bids are invited from contractors for supply of material, Installation, Networking, Transportation, Fixing, Trenching, and Laying of cable, related to Indoor and outdoor work for South East section in Mumbai Division of Central railway.

2. TENDER SCHEDULE:

| | | |
|----------------------------------------------|---|-------------------------|
| Date of Publishing on Puncom Website | : | 13-01-2019 |
| Last date of Submission of sealed Quotations | : | 22-01-2019 at 12:00 Hrs |
| Date of Opening of sealed quotations | : | 22-01-2019 at 12:30 Hrs |

3. ELIGIBILITY CRITERIA:

- a. The contractors must have valid PAN & GST No. and copy of same will be submitted along with the bid.
- b. The contractor should deploy technical manpower (Engineers, Diploma Holder as well as Labour) as per Railway requirement who is proficient in outdoor work.
- c. The contractor should have the ability to meet the running expenditure to execute this contract.
- d. The contractor should have not been blacklisted by any Govt. / PSUs or any other agencies earlier.

4. TERMS & CONDITIONS:

- a. All terms and conditions as per Railway's :- LOA NO CR/BB/TELE/2018/38 dated 15-11-2018 shall be applicable on contractor on back-to-back basis.
- b. Quoted rate should be inclusive of all applicable Taxes, transportation charges from the Railway store to sites and returning of leftover materials to Railways stores. Puncom will deduct only TDS from your running Bills. Contractor will submit IGST paid invoices for the items which fall in the category of supply as well as installation.
- c. The Security amount of 5% of the awarded work in the form of BG /FDR will be submitted by successful bidder
- d. The contractor should be ready to work on back-to-back LD / penalty conditions of the railway, in case work is being delayed by the sub - contractor without any justification.
- e. The contractor shall comply with all the provisions of GST , Income Tax or other taxes as applicable in the concerned state. Any penalty / fine / interest etc. for non-compliance for the laws shall be borne by the contractor.
- f. The contractor shall comply with all the provisions of local Labour laws.
- g. During maintenance period of one year, any failure related to executed work which was awarded by Puncom shall be rectified by contractor free of cost.
- h. Payment will be on back to back basis i.e Puncom will release the payment to contractor, when Puncom will get the payment from railways.

- i. Completion period for completion the entire work is Two months or as per requirement of Central Railways.
- j. PUNCOM reserves all rights to accept or reject wholly or partially any or all quotations at any time prior to award of contract without assigning any reasons and without incurring any liability of Puncom's action on the above grounds, to the affected parties .
- k. PUNCOM reserves the right to distribute the job among more than one eligible party.
- l. PUNCOM reserves the right to increase or decrease the value of contract by adding the additional work up to 25%.
- m. PUNCOM reserves the right to offer complete or partial work to the contractor.
- n. PUNCOM can reject the work awarded to contractor, in case the performance of the contractor is found unsatisfactory.
- o. Contractor must furnished the completed contact address and bank details in his Bid.

5. HOW TO APPLY

- a. Contractor should submit its prices in the sealed cover and prices should only be mentioned on the scope of work attached at Annexure- I. All conditions of tender documents must be complied by contractor and each page of Tender Document must be signed by the contractor.
- b. Contractor must ensure that all documents under eligibility conditions to be submitted along with the bid.
- c. Interested contractors may submit their offers in a sealed envelope Super-scribed as Ref.:- Tender No. : - PMD-FI-4.1.1450 / Tender dated 13-01-2019. TYPE OF WORK : supply of material, Installation, Networking, Transportation, Fixing, Trenching, and Laying of cable, related to Indoor and outdoor work for South East section in Mumbai Division of Central railway should be addressed to Head Projects PUNJAB COMMUNICATIONS LIMITED, B-91, PHASE VIII, INDUSTRIAL AREA, S.A.S. NAGAR (CHANDIGARH) – 160071. In case of any query, the parties may contact Head Projects. Phone :0172- 2237101(4 lines), 0172- 0172-5022901 (4 Lines) , 2237133 (Direct), E-MAIL : projects@puncom.com. www.puncom.com

6. EVALUATION

- a. Quotations must be received by the designated authority at the address specified not later than 12:00 hours on due date. The Puncom may at its discretion, extend this due date and time for the submission of quotations.
- b. Any quotation received by the Puncom after the due date and time for submission of quotations prescribed by the Puncom shall be rejected and returned unopened to the bidder.
- c. Puncom shall evaluate in detail and compare the quotations as per the eligibility conditions laid down in this document.
- d. Work will be allotted to Party, who has quoted lowest prices and meets all eligibility conditions laid down by Puncom.

Schedule of work

| Sr. No. | Description of Schedule | Unit | Qty | Rate (Rs.) | Total Amount |
|-----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------|-------------------|---------------------|
| 1 | Installation, wiring & Testing of 2 MB programmable primary digital drop insert multiplexer conforming as per railway requirement inclusive Transportation from Railway's .store to Sites. | Set | 25 | | |
| 2 | Installation, wiring & Testing of managed SDH STM-1 ADM's/ MADM's as per instruction of Site Engineer of Railways inclusive Transportation from Railway's .store to Sites. | Nos | 2 | | |
| 3 | Supply of GI pipe 100mm, B class as required by railway with socket & Fitting to railway store. | Mtr | 60 | | |
| 4 | Supply of permanently lubricated HDPE pipe as per railway requirement. | Mtrs | 500 | | |
| 5 | Laying of OFC cable through HDPE pipes as per approved cable route plan by Railway inclusive Transportation from Railway's .store to Sites.. | Mtrs | 500 | | |
| 6 | Supply of RCC PIPES 150mm dia along with collars NP type as per Railway requirement to Raiway store. | Mtrs | 50 | | |
| 7 | Laying of RCC PIPES conforming to route plan by Railway. inclusive of transportation from store to sites. | Mtrs | 50 | | |
| 8 | Fixing of GI pipes for crossing the culverts, bridges etc. and concreting as per instruction of Site Engineer of Railways inclusive of transportation from store to sites. | Mtrs | 60 | | |
| 9 | Supply of thermo shrinkable jointing kits as per Railway requirement to Raiway store. | Nos | 20 | | |
| 10 | Fixing of UTP I/O & termination with RJ-45 connector as per instruction of Site Engineer of Railways inclusive of transportation from Railway store to sites. | Nos | 50 | | |
| 11 | Excavation of trench 1.2 mtr deep 300 mm wide at the bottom along main line/suburban track as per instruction of Site Engineer of Railways | Kms | 2 | | |
| 12 | Excavation of cable trench 1.2 mtr deep and 300 mm wide at the bottom of rail/track crossing. as per instruction of Site Engineer of Railways | Mtrs | 100 | | |
| 13 | Excavation of cable trench 300 mm wide at the bottom and the 1.2 Meter deep and road crossing by digging the road. as per instruction of Site Engineer of Railways inclusive Transportation from Railway's store to Sites. | Mtrs | 200 | | |
| 14 | Laying of cables as per approved cable route plan in the excavated trench inclusive of transportation from store to sites. | Kms | 2 | | |
| 15 | Supply installation & testing of maintenance free earthing as per instruction of Site Engineer of Railways inclusive of transportation from store to sites.. | Nos | 2 | | |
| 16 | Supply of insulated flat copper strip of thickness 3mm, width 25mm, 24 feet long in running feet with nut bolt to railway store. | Kg | 10 | | |
| 17 | Fixing of PVC pipe/casing with capping on wall & below platform shed as per instruction of Site Engineer of Railways inclusive of transportation from store to sites.. | mtrs | 400 | | |
| Total value of works. | | | | | |